

**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**CLASS – IV
SPACESAVER
CUSHION TIRE**

CLASS IV - CONTENTS

SERIES – MODEL	PAGE
D010 – S25, 30, 35XM, 40XMS	2
D187 – S40, 45, 50, 55XMS, S55, 60, 65XM	9
E004 – S70, 80, 100, 120XM	14
B024 – S135-155XL2	20
B024 - S155XL2-32 (SPECIAL CONFIGURATION)	32
B024 - S155XL2-SP (SPECIAL CONFIGURATION)	34
B024 - S180XL2 (SPECIAL CONFIGURATION)	35
B024 - S200XL2 (SPECIAL CONFIGURATION)	37

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

**S25, 30, 35XM, 40XMS
SIT DOWN
COUNTERBALANCED
CUSHION TIRE
SERIES CODE D010**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

Spacesaver – Class IV
D010 – S25, 30, 35XM, 40XMS

ACCUMULATOR

Note: Cowl mounted components may require restricted back tilt; contact SPED.

1-quart piston type.....	Q001-02	\$685.	16
Hydra Smooth 1-quart piston type	Q001-06	\$1,560.	16

ALTERNATOR

30 Amp output with integral regulator – brushes and bearings are sealed.

UL APPROVED. Standard on units with UL type GS, LPS, option on order.

Requires Mazda gas or LP gas engine option on order.....	Q006-15	\$710.	10
--	---------	--------	----

BELLY PAN

Acts as splashguard only – does not completely enclose underside of frame.

Includes cutouts for access to drain plugs SPED

ELECTRIC ATTACHMENT GROUP

- A. Each electric attachment group special item listed:
1. does NOT include a SOLENOID valve. Solenoids are to be provided by the dealer or supplied as part of the attachment.
 2. is for FACTORY INSTALLATION only.
 3. requires a mast, applicable hydraulic control valve, applicable hose group and the special placard item on order.
 4. VOIDS UL APPROVAL.
- B. See Price List for 5 function option alternatives. For questions or other alternatives, contact SPED.

3 Auxiliary Function Attachment - All internal routing through mast. 2 functions lever actuated and 1 function controlled via solenoid actuation. Includes necessary electrical cable, 4 function hydraulic hoses, components required for internal routing of electrical cable, and operator control switching for actuation of solenoid.

Requires 4-function valve and 4-function hose group.....	Q074-05	\$1,420.	16
--	---------	----------	----

ENGINE AIR FILTER

Cyclopac type heavy-duty air cleaner element replacing standard element under hood.

Requires Mazda engine option on order.

NOT AVAILABLE w/CARB Emissions Compliant Engine.....	Q004-05	\$500.	4
--	---------	--------	---

Precleaner mounted on overhead guard. NOT AVAILABLE with Cab.

NOT AVAILABLE w/CARB Emissions Compliant Engine.....	Q004-04	\$525.	14
--	---------	--------	----

NOTE: For Foundry Construction Item Q004-04 and Q004-05 are included.

ENGINE SHUTDOWN SYSTEM

High water and transmission temperature and low oil pressure conditions. UL APPROVED.

Requires LP gas engine	Q069-02	\$450.	8
------------------------------	---------	--------	---

Seat actuated if operator does NOT set park brake. VOIDS UL APPROVAL.

Requires gas engine	Q069-08	\$495.	8
---------------------------	---------	--------	---

Requires LP gas engine	Q069-09	\$495.	8
------------------------------	---------	--------	---

Seat actuated if operator does NOT return the column mounted directional control

lever to the neutral position. Requires column lever option on order. VOIDS UL APPROVAL.

Requires gas engine	Q069-11	\$630.	8
---------------------------	---------	--------	---

Requires LP gas engine	Q069-12	\$630.	8
------------------------------	---------	--------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

**S25, 30, 35XM, 40XMS
SIT DOWN
COUNTERBALANCED
CUSHION TIRE
SERIES CODE D010**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

ENGINE WARNING SYSTEM

High water temperature and low oil pressure conditions.

Includes warning light and buzzer – VOIDS UL APPROVAL	Q180-01	\$940.	10
---	---------	--------	----

EXHAUST SYSTEM

2-way Catalytic muffler replaces standard or catalyst added in exhaust line.

VOIDS UL APPROVAL. Requires gas or LP gas engine on order	Q068-10	\$850.	16
---	---------	--------	----

FILTER

Hydraulic tank breather filter- - 10-micron filter replaces standard	Q120-02	\$285.	3
--	---------	--------	---

FIRE EXTINGUISHER

5 lb. dry chemical	Q080-01	\$255.	4
--------------------------	---------	--------	---

5 lb. CO ₂	Q080-02	\$520.	4
-----------------------------	---------	--------	---

FORK

See Introduction for Notes.

FORK-HOOK TYPE, PALLET STYLE

Specify length in 2" increments on order.

ITA

Class	Section	Length			
II	40mm x 100mm	32"-34"	Q086-36	\$415. pr.	12
	(1.5" x 4")	38"-40"	Q086-37	\$430. pr.	12
		44"-46"	Q086-38	\$440. pr.	12
		50"-52"	Q086-39	\$455. pr.	12
		56"-58"	Q086-40	\$475. pr.	12

FORK-HOOK TYPE, POLISHED & TAPERED STYLE- FULL TOP TAPER

Specify length in 2" increments on order.

ITA

Class	Section	Length			
II	40mm x 100 mm	30"	Q380-01	\$430. pr.	12
	(1.5"x 4")	32"-34"	Q380-02	\$455. pr.	12
		38"-40"	Q380-03	\$470. pr.	12
		44"-46"	Q380-04	\$495. pr.	12
		50"-54"	Q380-05	\$520. pr.	12
		56"-60"	Q380-06	\$540. pr.	12
		62"-72"	Q380-07	\$645. pr.	12

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY **SPED PRICE LIST** **APPLICATIONS ENGINEERING DEPARTMENT**

S25, 30, 35XM, 40XMS
SIT DOWN
COUNTERBALANCED
CUSHION TIRE
SERIES CODE D010

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

FORK-HOOK TYPE, POLISHED & TAPERED STYLE- FULL BOTTOM TAPER

Specify length in 2" increments on order.

ITA

Class	Section	Length			
II	40mm x 100 mm (1.5"x 4")	30"	Q380-40	\$430. pr.	12
		32"-34"	Q380-41	\$455. pr.	12
		38"-40"	Q380-42	\$470. pr.	12
		44"-46"	Q380-43	\$495. pr.	12
		50"-54"	Q380-44	\$520. pr.	12
		56"-60"	Q380-45	\$540. pr.	12
		62"-72"	Q380-46	\$645. pr.	12

FOUNDRY CONSTRUCTION

Standard Foundry Package NOT AVAILABLE on units with CAB.

Includes:

- 10 micron hydraulic tank breather filter (see Filter)
- 30-amp alternator with sealed brushes and bearings with integral regulator (see Alternator)
- Overhead mounted precleaner for engine air cleaner (Includes Cyclopac type Heavy Duty Air Cleaner Element)

Options:

- Fire resistant hydraulic fluid (See Hydraulic Fluid)
- Magnetic drain plug in hydraulic tank to attract metal particles (Contact SPED)
- Engine air restriction indicator (see Indicator)

Package:

NOT COMPATIBLE w/CARB Emissions Compliant Engine

Requires Mazda gas or LP gas engine and UL type G or LP Q349-18 \$1,975. 14

Requires Mazda gas or LP gas engine and UL type GS or LPS..... Q349-20 \$1,725. 14

FUEL SYSTEM

Note: CHANGES TO THE FUEL SYSTEM MAY RESULT IN VARIANCES TO PUBLISHED VALUES; CONTACT SPED IF CRITICAL.

Dual fuel – gas and LP gas. Includes production LP tank mounting bracket and LP fuel tank.

Requires gas engine option on order. Q095-04 \$1,685. 6

FUEL TANK

LP gas tank – aluminum. Requires LP gas engine option on order. FACTORY INSTALLED ONLY.

33.5# ICC tank Q060-02 \$435. 12

GROUND STRAP (STATIC STRAP)

Prevents build up of static electricity on frame and steer axle Q108-01 \$85. 2

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

**S25, 30, 35XM, 40XMS
SIT DOWN
COUNTERBALANCED
CUSHION TIRE
SERIES CODE D010**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

HYDRAULIC FITTING-QUICK DISCONNECT

Male and female hydraulic fittings and tubes to allow an attachment to be quickly disconnected from the hydraulic supply for removal. Includes complete quick disconnect fittings for each function. Not normally required for integrally mounted attachments. 4-function disconnect requires 4-function hose group and control valve on order.

Vista 2-Stage Limited Free Lift Mast

One pair disconnect	-3 Function – High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-16	\$600.	14
	-4 Function – High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-17	\$600.	14
Two pair disconnects	-4 Function - High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-18	\$1,150.	14

Vista 2-Stage Full Free Lift Mast

One pair disconnect	-3 Function – High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-19	\$615.	14
	-4 Function– High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-20	\$615.	14
Two pair disconnects	-4 Function- High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-21	\$1,170.	14

Vista 3-Stage Full Free Lift Mast

One pair disconnect	-3 Function– High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-22	\$570.	14
	-4 Function– High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-23	\$570.	14
Two pair disconnects	-4 Function High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-24	\$825.	14

Other Mast Styles or 5 function hose groups SPED

HYDRAULIC FLUID

Fire Resistant - FACTORY INSTALLED.

CANNOT BE INSTALLED ON STOCK BASIC.	Q140-01	\$2,880.	18
--	---------	----------	----

HYDRAULIC PRESSURE REGULATOR

3 position with gauge - used to regulate the pressure in the hydraulic attachment clamping circuit. 1st & 2nd positions are 50-1000 psi and the 3rd position is 500-3000 psi.

Requires applicable control valve and hose group on order.....	Q203-01	\$2,250.	12
--	---------	----------	----

LIGHT-HEAD

NOT AVAILABLE with Price List light options (consult Truck Price List for light options offered prior to quoting to a customer).

UL APPROVED for all classifications. Maximum order quantity is 2 per truck.

Headlight – separate switch actuated	Q401-01	\$415. ea.	8
--	---------	------------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY **SPED PRICE LIST** **APPLICATIONS ENGINEERING DEPARTMENT**

S25, 30, 35XM, 40XMS
SIT DOWN
COUNTERBALANCED
CUSHION TIRE
SERIES CODE D010

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

LIGHT-REAR DRIVING

NOT AVAILABLE with Price List light options (consult Truck Price List for light options offered prior to quoting to a customer).

UL APPROVED for all classifications. Maximum order quantity is 2 per truck.

Rear drive light – separate switch actuated	Q402-01	\$230. ea.	8
---	---------	------------	---

LIGHT-STROBE

Continuous strobe, key switch actuated, UL APPROVED.

Overhead guard top mounted – increases truck height approximately 7".

Red.....	Q393-13	\$420.	12
----------	---------	--------	----

Amber.....	Q393-14	\$420.	12
------------	---------	--------	----

Mounted below overhead guard top.

Red.....	Q393-15	\$420.	12
----------	---------	--------	----

Amber.....	P.L.		
------------	------	--	--

LINT/COTTON CONSTRUCTION

Features suggested for use in lint, cotton, paper, paper recycling or other fibrous materials applications. Contact SPED for assistance with feature selections for a particular application.

Package features:

- Insulated exhaust
- Sealed bearings in alternator
- Inching pedal modification
- Screened side panels and kickplate
- Booted electrical terminals
- Spark arresting exhaust

Requires UL Classification GS or LPS option on order.

Package factory installed; requires Open Core Radiator option on order.

NOT AVAILABLE on stock basics.....	Q130-01	\$3,000.	14
------------------------------------	---------	----------	----

LOAD BACKREST EXTENSION

See Introduction for Notes.

Carriage or Attachment Width	Height 36"	42"	48"	60"	
36"	Q166-49 \$340.	Q166-50 355.	Q166-51 330.	Q166-52 400.	14

LUBRICANT/COATING

Electrical terminals sprayed with waterproof plastic	Q145-01	\$270.	6
--	---------	--------	---


Unpainted parts coated with low temperature grease.....	Q145-02	\$270.	6
---	---------	--------	---

Lift chains saturated with low temperature grease-requires Mast.....	Q145-03	\$270.	6
--	---------	--------	---

MIRROR

Rearview mirror. NOT intended for reverse driving.	Q177-01	\$150.	8
---	---------	--------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

**S25, 30, 35XM, 40XMS
SIT DOWN
COUNTERBALANCED
CUSHION TIRE
SERIES CODE D010**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

NAMEPLATE

Additional Nameplate FACTORY INSTALLED. Nameplates will be provided with one load center giving the rating at maximum fork height and the maximum possible rating at a lower fork height. For NOT INSTALLED nameplates, submit "DEALER REQUEST FOR NAMEPLATE" form.

Metric Values with English Values Referenced	Q198-03	\$75. net	4
--	---------	-----------	---

OVERHEAD GUARD

Wire mesh added to top increases height approximately 3/8"	Q153-01	\$250.	10
--	---------	--------	----

Order for standard or special overhead guard.

OVERHEAD GUARD-LOWERED

OSHA recommended operator clearance from depressed seat to underside of overhead guard is 39" minimum. Low profile seat is recommended. NOT AVAILABLE with semi-suspension or full suspension seats.

Note: (+/- 0.75") tolerance for Overall Height (OAH)

79.12" OAH	Q385-05	\$650.	16
78.12" OAH (Requires Low-Profile Seat Option)	Q385-06	\$755.	16

OVERHEAD GUARD-RAISED

Note: (+/- 0.75") tolerance for Overall Height (OAH)

84.12" OAH	Q384-05	\$325.	16
------------------	---------	--------	----

SEAT

Fabric covered non-suspension seat replacing vinyl covered non-suspension seat.

Includes seat adjustment and operator restraints.

Not recommended for outdoor applications without a cab.

Requires non-suspension seat option on order.	Q252-01	\$75.	12
--	---------	-------	----

SEAT-LOW PROFILE

Low profile seat replacing standard seat increases operator head clearance approximately 1".

Requires non-suspension seat option on order.

Vinyl covering	Q397-02	\$650.	12
Fabric covering	Q397-03	\$650.	12

SEAT-SUSPENSION

Semi-Suspension – Vinyl	Q065-01	\$565.	12
-------------------------------	---------	--------	----

Semi-Suspension – Cloth	Q065-02	\$615.	12
-------------------------------	---------	--------	----


TIRES

See Introduction for Notes.

TIRE-DRIVE

Non-marking Smooth Tread Solid Drive. 18 x 7 x 12.1	P.L.		
Lug Tread Solid Drive. 18 x 6 x 12.1 (S25, S30 only)	Q319-18	\$280. pr.	12
Lug Tread Solid Drive. 18 x 7 x 12.1	Q319-25	\$290. pr.	12
Non-Marking Lug Tread Drive. 18 x 6 x 12.1 (S25-30 only)	Q319-32	\$315. pr.	12
Non-Marking Lug Tread Drive. 18 x 7 x 12.1	Q319-33	\$325. pr.	12

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S25, 30, 35XM, 40XMS
SIT DOWN
COUNTERBALANCED
CUSHION TIRE
SERIES CODE D010**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

TIRE-STEER

Non-marking Smooth Tread Solid Steer. 15 x 5 x 11.25	P.L.		
Lug Tread Solid Steer. 15 x 5 x 11.25.....	Q318-14	\$125. pr.	10
Non-Marking Lug Tread Solid Steer. 15 x 5 x 11.25.....	Q318-21	\$200. pr.	10

TRANSMISSION

Auxiliary transmission oil cooler.	Q297-03	\$650.	12
---	---------	--------	----

TREAD

Standard Tread with Hi-Lift Mast and Reduced Capacity Acceptance

Allows the use of Standard Tread in conjunction with Hi-Lift Mast.

The Dealer and Customer understand that there will be a reduction in the capacity of the truck.

Dealers should contact Applications Engineering for specific capacity ratings.

.....	Q206-98	\$0.	Prod.
-------	---------	------	-------

WARNING SYSTEM

Backup Alarm.	P.L.		
--------------------	------	--	--

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S40, 45, 50, 55XMS
S55, 60, 65XM
SIT DOWN
COUNTERBALANCED
SERIES CODE D187**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

D187 – S40, 45, 50, 55XMS, S55, 60, 65XM

ACCUMULATOR

Note: Cowl mounted components may require restricted back tilt; contact SPED.

Parker 1-quart piston type	Q001-02	\$1,225.	8
Parker 2-quart piston type	Q001-03	\$1,750.	8
Hydra Smooth 1-quart piston type	Q001-06	\$1,560.	8

APPROVAL

Reduced Truck Capacity Acceptance. Allows the use of standard tread in conjunction with hi-lift mast.

See [TREAD](#).

ENGINE SHUTDOWN SYSTEM

Seat actuated if operator leaves the seat and the set park brake is NOT set. For gas, LP gas, or Dual Fuel.

VOIDS UL APPROVAL.	Q069-08	\$735.	8
-------------------------	---------	--------	---

Seat actuated if operator does NOT return the column mounted directional control lever to the neutral position.
Requires column lever and LP gas engine on order.

VOIDS UL APPROVAL.	Q069-12	\$735.	8
-------------------------	---------	--------	---

EXHAUST SYSTEM

Catalytic muffler replaces standard muffler - Requires gas or LP gas engine on order

UL APPROVED. Not available with UL classification LPS or GS	Q068-12	\$1,200	16
---	---------	---------	----

Overhead exhaust. Not available with UL classification LPS or GS or Drive Thru Rack Overhead Guard.
Requires LP gas engine on order. NOT AVAILABLE with CARB Emissions Compliant Engine.

Not available on S55XMS. VOIDS UL APPROVAL.	Q068-02	\$2,590	10
--	---------	---------	----

FIRE EXTINGUISHER

5 lb. dry chemical	Q080-01	\$350.	4
5 lb. CO ₂	Q080-02	\$520.	4

FORK

See Introduction for Notes.

FORK-HOOK TYPE, PALLET STYLE

1.5" x 4 x 40" Long – Class II	Q086-37	\$450. pr.	6
--------------------------------------	---------	------------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S40, 45, 50, 55XMS
S55, 60, 65XM
SIT DOWN
COUNTERBALANCED
SERIES CODE D187**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

FOUNDRY CONSTRUCTION

Foundry Package NOT AVAILABLE on units with CAB.

Includes:

- 10-micron hydraulic tank breather filter (standard).
- 30-45 amp alternator with sealed brushes and bearings with integral regulator.
- Overhead mounted precleaner for engine air cleaner.
- Cyclopac type heavy-duty air cleaner element.

Options:

- Fire resistant hydraulic fluid (Contact SPED)
- Engine air restriction indicator (Contact SPED)
- Open CORE Radiator (See Price List)

Package:

Requires Mazda gas or LP gas engine and UL type G or LPS options.

NOT AVAILABLE w/CARB Emissions Compliant Engine.....	Q349-18	\$2,090.	14
--	---------	----------	----

Requires GM gas or LP gas engine and UL type G or LP	Q349-20	\$2,090.	14
--	---------	----------	----

FUEL SYSTEM

Fold Down LP Bracket. Bracket folds down over rear of counterweight.

UL Approved.	Q095-10	\$1,050.	9
-------------------	---------	----------	---

FUEL TANK

LP gas tank – aluminum. Requires LP gas engine option on order.

FACTORY INSTALLED ONLY

33.5# ICC tank	Q060-02	\$360	6
----------------------	---------	-------	---

GROUND STRAP (STATIC STRAP)

Prevents build up of static electricity on frame and steer axle.

Standard with price list option non-marking tires	Q108-01	\$95.	2
---	---------	-------	---

HOOD

Hood-Expanded metal vents added to side panels	Q134-01	\$360	9
--	---------	-------	---

HOSE GROUP-3 FUNCTION

2 Hoses Routed Internal (1 Aux)

For Special 2-Stg FFL and 3-Stg FFL Mast	Q373-10	\$760.	8
--	---------	--------	---

For Special 2-Stg LFL Mast.....	Q373-11	\$625.	8
---------------------------------	---------	--------	---

For Special 4-Stg FFL Mast	Q373-12	\$915.	8
----------------------------------	---------	--------	---

HOSE GROUP-4 FUNCTION

4 Hoses Routed Internal (2 Aux)

For Special 2-Stg FFL and 3-Stg FFL Mast	Q374-13	\$1,095.	8
--	---------	----------	---

For Special 2-Stg LFL Mast.....	Q374-14	\$860.	8
---------------------------------	---------	--------	---

For Special 4-Stg FFL Mast	Q374-15	\$1,460.	8
----------------------------------	---------	----------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY **SPED PRICE LIST** **APPLICATIONS ENGINEERING DEPARTMENT**

S40, 45, 50, 55XMS
S55, 60, 65XM
SIT DOWN
COUNTERBALANCED
SERIES CODE D187

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

HYDRAULIC FITTING-QUICK DISCONNECT

Male and female hydraulic fittings and tubes to allow an attachment to be quickly disconnected from the hydraulic supply for removal. Includes complete quick disconnect fittings for each function. Not normally required for integrally mounted attachments. 3-function disconnect requires 3-function hose group and control valve on order. 4-function disconnect requires 4-function hose group and control valve on order.

Vista 2-Stage Limited Free Lift Mast

One pair disconnect	-3 Function – High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-16	\$700.	6
	-4 Function – High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-17	\$700.	6
Two pair disconnects	-4 Function - High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-18	\$1,370.	6

Vista 2-Stage Full Free Lift Mast

One pair disconnect	-3 Function – High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-19	\$700.	6
	-4 Function– High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-20	\$700.	6
Two pair disconnects	-4 Function- High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-21	\$1,370.	6

Vista 3-Stage Full Free Lift Mast

One pair disconnect	-3 Function– High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-22	\$700.	6
	-4 Function– High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-23	\$700.	6
Two pair disconnects	-4 Function High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-24	\$1,370.	6

Vista 4-Stage Full Free Lift Mast

One pair disconnect	-3 Function– High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-28	\$700.	6
	-4 Function– High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-29	\$700.	6
Two pair disconnects	-4 Function High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-30	\$1,370.	6

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S40, 45, 50, 55XMS
S55, 60, 65XM
SIT DOWN
COUNTERBALANCED
SERIES CODE D187**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

LIGHT-STROBE

Continuous strobe, key switch actuated, UL APPROVED.

Overhead guard top mounted – increases truck height approximately 7".

Red.....	Q393-13	\$525.	8
----------	---------	--------	---

Amber.....	Q393-14	\$525.	8
------------	---------	--------	---

Mounted below overhead guard top.

Red.....	Q393-15	\$525.	8
----------	---------	--------	---

Amber.....	PL		
------------	----	--	--

LIGHT-TURN SIGNAL

2 rear turn signals. Requires Brake Lights with Backup Lights on order.

Available with rear drive light item Q402-01.UL APPROVED.....	Q404-03	\$250.	8
---	---------	--------	---

LINT/COTTON CONSTRUCTION

Features suggested for use in lint, cotton, paper, paper recycling or other fibrous materials applications. Contact SPED for assistance with feature selections for a particular application.

Package features:

- Rubber boot added to air intake to reroute airflow through engine compartment and radiator to minimize pickup of small debris from floor when required.
- Screened holes added to hood and kickboard when required
- Inching pedal overlap modification when required
- Insulated wrap on exhaust.

Requires UL Classification GS or LPS option on order.

Package factory installed; requires open core radiator option on order.

NOT AVAILABLE on stock basics.....	Q130-01	\$1,975.	10
------------------------------------	---------	----------	----

LOAD BACKREST EXTENSION

See Introduction for Notes.

Load Backrest Extension – 38.5" W x 60" High	Q166-14	\$755.	8
--	---------	--------	---

MIRROR

Rearview mirror – Mounted on left hand overhand guard leg.

NOT intended for reverse driving.	Q177-01	\$150.	8
--	---------	--------	---

NAMEPLATE

Additional Nameplate FACTORY INSTALLED. Nameplates will be provided with one load center giving the rating at maximum fork height and the maximum possible rating at a lower fork height. For NOT INSTALLED nameplates, submit "DEALER REQUEST FOR NAMEPLATE" form.

Metric Values with English Values Referenced	Q198-03	\$75 net	4
--	---------	----------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

S40, 45, 50, 55XMS
S55, 60, 65XM
SIT DOWN
COUNTERBALANCED
SERIES CODE D187

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

PAINT

ONE COLOR-Lead/Chromate free enamel paint on all normally painted exterior surfaces only. Exterior paint may be applied over standard color pre-painted surfaces. Does NOT include interior surfaces. Paint color panel/chip must accompany orders for Non-Hyster colors. Hyster paint vendor to match color. Contrasting features, color and decals provided at Hyster's discretion. Hyster reserves the right to reject requirements for UNUSUAL NON-STANDARD Paints, PAINT SCHEMES or paints requiring SPECIAL APPLICATION TECHNIQUE. For paint schemes not listed or for special colors on NOT INSTALLED options or special items, contact SPED.

Specify one paint color number for each item ordered.

Color Number: 1 = Hyster yellow

2 = Hyster white

3 = Hyster red

4 = Hyster black

5 = Non-Hyster color. Requires color panel/chip with order! Orders received without such will be delayed!

Complete Truck(not forks or cab)-replace standard colors.....	Q191-08	\$1,145.	12
Chassis/counterweight/hood -replace yellow & black	Q191-09	\$705.	12
Chassis/counterweight/hood -replace yellow only.....	Q191-10	\$670.	12
Overhead Guard -replace black only	Q191-05	\$175.	12
Wheels -replace standard color	Q191-12	\$160.	12
Load Backrest -replace standard color	Q191-14	\$120.	12
Forks -replace standard color	Q191-06	\$120.	12

SEAT-LOW PROFILE

Low profile seat replacing standard seat increases operator head clearance approximately 1".

Vinyl covered.....	Q397-02	\$975.	12
--------------------	---------	--------	----

SEAT-SUSPENSION

Hyster semi-suspension style seat replacing standard seat. Reduces operator head clearance ½". Standard (raised) overhead guard is recommended to compensate for the operator head clearance reduction. Consult technical guide for head clearance information. OSHA recommended operator head clearance from depressed seat to underside of overhead guard is 39" minimum. Includes seat adjustment and operator restraints.

Vinyl covered.....	Q065-01	\$575.	12
--------------------	---------	--------	----

Cloth covered	Q065-02	\$700.	12
---------------------	---------	--------	----

TRACTION SPEED LIMIT

Contact Applications Engineering.

TRANSMISSION

Auxiliary transmission oil cooler.....	Q297-03	\$700.	8
--	---------	--------	---

TREAD

Reduced Truck Capacity Acceptance. Allows the use of standard tread in conjunction with hi-lift mast.

The Dealer and Customer understand that there will be a reduction in the capacity of the truck.

Dealers should contact SPED for specific capacity ratings	Q206-98	\$0.	0
---	---------	------	---

WARNING SYSTEM

BACKUP ALARMPL

BELL - WHEEL MOUNTED. Extends 3" beyond wheel.

Sounds when truck is traveling in reverse.	Q222-08	\$360.	8
---	---------	--------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY **SPED PRICE LIST** **APPLICATIONS ENGINEERING DEPARTMENT**

S70, 80, 100, 120XM
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE E004

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

E004 – S70, 80, 100, 120XM

ACCUMULATOR

Note: Cowl mounted components may require restricted back tilt; contact SPED.

Parker 2-quart piston type	Q001-03	\$1,400.	16
Parker 4-quart piston type	Q001-05	\$1,730.	16
Hydra Smooth 1-quart piston type	PL		
Hydra Smooth 2-quart piston type	Q001-07	\$1,400.	16

BRAKES

Mico Accumlock - supplements existing brake system. Acts as a holding device for truck until control lever on instrument panel is manually turned off and brake pedal is tapped lightly. Includes low-pressure warning light.

VOIDS UL APPROVAL	Q003-07	\$1,670.	14
-------------------------	---------	----------	----

CARRIAGE

See Introduction for Notes.

Contact Applications Engineering for special carriage options.

COLD START AID

Engine Block Heater - Requires 110 Volt AC outlet.....	Q048-01	\$475.	15
--	---------	--------	----

COOLING SYSTEM

Radiator cap – LEV-R-VENT manual pressure relief type.

Factory Installed	Q236-01	\$55.	2
Field Installed		Parts	

ENGINE

Severe Duty Engine-GM 4.3L LT – LPG only. For applications where multiple shifts are required with little to no cool down period for lift trucks.

Requires GM LP Gas engine option on order.	Q063-01	\$500.	12
---	---------	--------	----

ENGINE SHUTDOWN SYSTEM

High water temperature and low oil pressure conditions. UL Approved.Std

Seat actuated if operator does NOT set park brake. VOIDS UL APPROVAL.

Requires gas engine or dual fuel system	Q069-08	\$700.	8
Requires LP gas engine	Q069-09	\$700.	8
Requires diesel engine	Q069-10	\$700.	8

Seat actuated if operator does NOT return the column mounted directional control lever to the neutral position.

Requires powershift transmission and column lever options on order.

VOIDS UL APPROVAL.


Requires gas engine or dual fuel system	Q069-11	\$700.	8
Requires LP gas engine	Q069-12	\$700.	8
Requires diesel engine	Q069-13	\$700.	8

EXHAUST SYSTEM

Catalytic muffler replaces standard or catalyst added in exhaust line.

Requires Gas or LP engine on order. UL APPROVED.....	Q068-10	\$1,650.	6
--	---------	----------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY **SPED PRICE LIST** **APPLICATIONS ENGINEERING DEPARTMENT**

S70, 80, 100, 120XM
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE E004

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

FILTER

Hydraulic tank breather filter 10-micron Std.

FIRE EXTINGUISHER

5 lb. dry chemical	Q080-01	\$340.	6
5 lb. CO ₂	Q080-02	\$500.	6
10 lb. dry chemical	Q080-03	\$365.	6
10 lb. CO ₂	Q080-04	\$540.	6

FORK

See Introduction for Notes.

Contact Applications Engineering.

FOUNDRY CONSTRUCTION

Foundry Package NOT AVAILABLE on units with CAB.

Includes:

- 10 micron hydraulic tank breather filter (Std.)
- Air restriction indicator (Std with Premium Instrumentation package)
- Square wave radiator (Std.)
- Pusher type fan (Std.)
- (2) Lube fittings on each tilt pin (Std.)
- 45 amp alternator with sealed brushes and bearings with integral regulator (Std. with LPS)

If additional items are required in the application (e.g. booted tilt/steer cylinders, vented hood and kick plate), contact Applications Engineering.

Requires Premium Instrumentation (Option 017-02), Heavy Duty Precleaner (Option 078-02), and UL Classification G/LP/D (Option 056-01) on order.....	Q349-26	\$435.	12
--	---------	--------	----

Note: If the required price list options listed above and UL classification LPS (Option 056-02) are on the order, no additional option is needed.

FUEL TANK

LP gas tank – aluminum. Requires LP gas engine option on order.

FACTORYINSTALLED ONLY – 43.5# ICC Tank	Q060-08	\$580.	12
--	---------	--------	----

GROUND STRAP (STATIC STRAP)

Prevents build up of static electricity on frame and steer axle	Q108-01	\$95.	6
---	---------	-------	---


HYDRAULIC FITTING-QUICK DISCONNECT

Male and female hydraulic fittings and tubes to allow an attachment to be quickly disconnected from the hydraulic supply for removal. Includes complete quick disconnect fittings for each function. Not normally required for integrally mounted attachments. 4-function disconnect requires 4-function hose group and control valve on order.

Vista 2-Stage Limited Free Lift Mast

One pair disconnect -3 Function – High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-16	\$650.	14
-4 Function – High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-17	\$650.	14

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

**S70, 80, 100, 120XM
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE E004**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

Two pair disconnects -4 Function - High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-18	\$1,225.	14
--	---------	----------	----

Vista 2-Stage Full Free Lift Mast

One pair disconnect -3 Function – High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-19	\$650.	14
--	---------	--------	----

-4 Function – The 4 th Function terminates at the top RIGHT side of carriage as part of the standard hose group when used with a Vista 2-Stage Full Free Lift mast. QD Fittings added to 4 th Function	Q187-20	\$400.	14
---	---------	--------	----

Two pair disconnects -4 Function - High Termination for 3 rd & 4 th function...Contact Application Engineering			
--	--	--	--

Vista 3-Stage Full Free Lift Mast

One pair disconnect -3 Function– High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-22	\$650.	14
---	---------	--------	----

-4 Function– High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-23	\$650.	14
---	---------	--------	----

Two pair disconnects -4 Function High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-24	\$1225.	14
--	---------	---------	----

HYDRAULIC PRESSURE REGULATOR

3-position with gauge.	PL		
-----------------------------	----	--	--

HYDRAULIC VALVE-LOAD PROTECTOR

Prevents lift chains from going slack after depositing a load with a clamping type attachment. Load protector	Q348-01	\$1,700.	10
--	---------	----------	----

INDICATOR

Air Cleaner Restriction Indicator Requires P. L. Standard Instrumentation Package 017-01.....	Q126-02	\$125.	10
--	---------	--------	----

Note: Included with P.L. Premium Instrumentation Package 017-02.

LIGHT-STROBE

Continuous strobe, key switch actuated, UL APPROVED.			
Overhead guard top mounted – increases truck height approximately 7".			
Red.....	Q393-13	\$560.	12
Amber.....	Q393-14	\$560.	12
Mounted below overhead guard top.			
Red.....	Q393-15	\$560.	12
Amber.....	PL		

Note: Strobe lights can be converted to Reverse operated. No tools required.

LIGHT-TURN SIGNAL

2 front and 2 rear turn signals. UL APPROVED	Q404-02	\$920.	14
2 rear turn signals only. UL APPROVED	Q404-03	\$775.	14

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S70, 80, 100, 120XM
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE E004**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

LINT/COTTON CONSTRUCTION

Paper Recycling Package - suggested for use in lint, cotton, paper, or other fibrous materials applications.

Requires LPS Approval option 056-02 on LPG units.

Requires: Premium Instrumentation option 017-02, Radiator Screen option 022-02 and High Mount Heavy Duty Air Precleaner option 078-02 on order for all engine options.

NOT available with Overhead (064-02) or Catalytic exhaust.

Contact SPED for assistance with feature selections for a particular application.

Special Package includes:

- Exhaust Wrap
- Vented Side Panels
- Vented Kickplate (on units without Cab)
- Fully Sealed, Heavy Duty Belly Pan and maintenance access door with pull cable opener
- Brake Line Guards
- Park Brake Cable Guard
- Steer Wheel Baffles
- Standard Square Wave Radiator
- Inch Pedal Overlap Modification

S70-120XM.	Q130-01	\$4,400.	16
-----------------	---------	----------	----

LOAD BACKREST EXTENSION

See Introduction for Notes.

Contact Applications Engineering.

MAST TILT CONTROL-2 WAY

Mast tilt restricted to zero degrees at any lift height unless overridden by operator.

2-way Tilt Limit System. VOIDS UL APPROVAL	Q285-10	\$2,180.	16
--	---------	----------	----

MAST TILT LIMITER

See Introduction for Notes.

MAST TILT-LIMITER BACK/FORWARD

Back and Forward tilt limiters are available in one-degree increments within the range shown.

Specify the required degree of back/forward tilt on order. Consult the Industrial Truck Price List for production offering and usage restrictions before quoting.

NOTE: If total degrees of tilt sums up greater than maximum P.L. total tilt, contact SPED for approval (i.e. 7° Forward + 8° Back = 15° Total tilt). FACTORY INSTALLED.

Minimum	Maximum			
4°	11°	Back Tilt.....	Q287-01	\$340. pr. 8
0°	11°	Forward Tilt	Q288-01	\$340. pr. 8

MAST TILT INDICATOR

Mechanical linkage system to indicate when the mast is vertical	Q286-01	\$920.	8
---	---------	--------	---

MAST TILT SPEED

Speed restrictor for use with load sustaining attachments to improve dynamic stability conditions.

Fitting type restrictor	Q096-02	\$280.	8
-------------------------------	---------	--------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S70, 80, 100, 120XM
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE E004**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

MIRROR

Rearview Mirror. Not intended for reverse driving.

Price List cab options do not include this mirror.....	Q177-01	\$130.	8
--	---------	--------	---

NAMEPLATE

Additional Nameplate FACTORY INSTALLED. Nameplates will be provided with one load center giving the rating at maximum fork height and the maximum possible rating at a lower fork height. For NOT INSTALLED nameplates, submit "DEALER REQUEST FOR NAMEPLATE" form.

Metric Values with English Values Referenced	Q198-03	\$75. net	4
--	---------	-----------	---

OVERHEAD GUARD-LOWERED/RAISED

Contact SPED with specific height needed.

OVERHEAD GUARD-RAIN TOP

Plexiglas Rain Top mounted to top of overhead guard.....	Q238-01	\$880.	14
--	---------	--------	----

PAINT

ONE COLOR-Lead/Chromate free enamel paint on all normally painted exterior surfaces only. Exterior paint may be applied over standard color prepainted surfaces. Does NOT include interior surfaces. Paint color panel/chip must accompany orders for Non-Hyster colors. Hyster paint vendor to match color. Contrasting features, color and decals provided at Hyster's discretion. Hyster reserves the right to reject requirements for UNUSUAL NON-STANDARD Paints, PAINT SCHEMES or paints requiring SPECIAL APPLICATION TECHNIQUE. For paint schemes not listed or for special colors on NOT INSTALLED options pr special items, contact SPED.

Specify one paint color number for each item ordered.

Color Number: 1 = Hyster yellow

2 = Hyster white

3 = Hyster red

4 = Hyster black

5 = Non-Hyster color. Requires color panel/chip with order! Orders received without such will be delayed!

Complete Truck (not forks or cab)-replace standard colors**	Q191-08	\$1,145.	12
Chassis/counterweight/hood -replace yellow & black**.....	Q191-09	\$705.	10
Chassis/counterweight/hood -replace yellow only**.....	Q191-10	\$670.	10
Overhead Guard -replace black only	Q191-05	\$175.	10
Wheels -replace standard color	Q191-12	\$160.	10
Load Backrest -replace standard color	Q191-14	\$120.	10
Forks -replace standard color	Q191-06	\$130. pr.	10

**Dash, Floorboard, Seat Pan and Radiator Cover NOT painted.

SEAT-SUSPENSION

Full Suspension

Swivel 12° Right / 6° Left. Requires minimum 87" OAH Overhead Guard on order.


Vinyl.....	Q398-11	\$710.	12
Cloth	Q398-10	\$750.	12

Semi-Suspension

Grammer GS-12 Semi-Suspension (reduces operator head clearance approximately 0.2").

Black Vinyl covering	Q398-02	\$505.	12
Black Fabric covering.....	Q398-03	\$545.	12

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S70, 80, 100, 120XM
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE E004**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

TIRES-DRIVE

Requires Static Strap Q108-01 on order – See [GROUND STRAP](#)

Lugged Non-Marking 22"x9"x16"	S70-80XMQ319-40	\$400. pr.	12
Lugged Non-Marking 22"x12"x16"	S100-120XMQ319-41	\$450. pr.	12

TIRES-STEER

Requires Static Strap Q108-01 on order – See [GROUND STRAP](#)

Lugged Non-Marking 18"x7"x12.1"	S70-80XMQ318-21	\$400. pr.	12
Lugged Non-Marking 18"x8"x12.1"	S100-120XMQ318-22	\$450. pr.	12

TRACTION SPEED LIMIT

Traction speed limited to approximately 8.0 MPH when traveling in either forward or reverse. Proximity sensor monitors frequency of the differential gear teeth. When truck is traveling faster than 8.0 MPH, speed is limited by sending a signal to the electronic governor. Full throttle is available provided the truck is traveling less than 8.0 MPH. Requires GM or LPG engine on order. VOIDS UL APPROVAL.....Q262-06 \$1,945. 18

Engine governed at reduced RPM to limit travel speed and reduce noise levels. Maximum engine RPM will be governed to reduced level by replacing standard electronic governor with special governor. Maximum travel, lift, and attachment speeds will be reduced from published specifications shown in technical guides.


Requires GM engine option on order.

2300 RPM maximum.....	Q262-08	\$370.	Prod. + 2
2100 RPM maximum.....	Q262-09	\$370.	Prod. + 2
1900 RPM maximum.....	Q262-10	\$370.	Prod. + 2

TRANSMISSION

Auxiliary Transmission Oil Cooler. Requires restricted backtilt.....	Q297-03	\$820.	12
--	---------	--------	----

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

B024 – S135-155XL2

ACCUMULATOR

Note: Cowl mounted components may require restricted back tilt; contact SPED.

Parker 1-quart piston type.....	Q001-02	\$600.	16
Parker 2-quart piston type.....	Q001-03	\$1,400.	16
Parker 4-quart piston type.....	Q001-05	\$1,730.	16
Hydra Smooth 1 quart piston type.....	Q001-06	\$1,560.	16
Hydra Smooth 2 quart piston type.....	Q001-07	\$1,975.	16

ALTERNATOR

45 Amp output with integral regulator – brushes and bearings are sealed.

UL APPROVED. Standard on units with UL type GS, LPS, or DS option on order.

Requires GM gas or LP gas engine option on order.....	Q006-16	\$525.	10
Requires Perkins diesel engine option on order	Q006-18	\$510.	10

ATTACHMENT

See Introduction for Notes.

ATTACHMENT-SIDESHIFT, HOOK TYPE

Note: All sideshifts listed require 3-function valve and 3-function hose group.

Refer to vendors (Cascade/Brudi) for Hang-on Hook Type Class IV SS Attachment.

INTEGRAL MOUNTING TO MAST

Mast	Width	ITA	Class			
Vista 2-Stage LFL	48"	IV.....	Q257-01	\$7,950.	16	
Vista 2-Stage LFL	48"	IV.....	Q257-02	\$7,950.	16	

BELLY PAN

Acts as splashguard only – does not completely enclose underside of frame.

Includes cutouts for access to drain plugs	Q026-01	\$1,075.	12
--	---------	----------	----

BRAKES


Micro Accumlock - supplements existing brake system. Acts as a holding device for truck until control lever on instrument panel is manually turned off and brake pedal is tapped lightly. Includes low-pressure warning light.

VOIDS UL APPROVAL	Q003-07	\$725.	14
-------------------------	---------	--------	----

CARRIAGE

See Introduction for Notes.

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

CARRIAGE-HOOK TYPE, VISTA 2-STAGE LIMITED FREE LIFT MAST

Width ITA

Class

54" IV	Q296-41	\$4,490.	14
60" IV	Q296-42	\$4,785.	14
78" IV	Q296-43	\$5,500.	14

CARRIAGE-HOOK TYPE, VISTA 3-STAGE FULL FREE LIFT MAST

Width ITA

Class

54" IV	Q467-25	\$4,490.	14
60" IV	Q467-26	\$4,785.	14
78" IV	Q467-30	\$5,500.	14

COLD START AID

Engine block heater requires 110 Volt AC outlet	Q048-01	\$790.	15
---	---------	--------	----

Ether start requires diesel engine option on order.

VOIDS UL APPROVAL	Q048-02	\$440.	15
-------------------------	---------	--------	----

COOLING SYSTEM

Radiator cap – LEV-R-VENT manual pressure relief type.

Factory installed	Q236-01	\$45.	2
Field installed P/N 1312753		Parts	

ELECTRIC ATTACHMENT GROUP

NOTES:

Each Electric Attachment Group special item listed:

- does NOT include a SOLENOID valve. Solenoids are to be provided by the dealer or supplied as part of the attachment.
- is for FACTORY INSTALLATION only.
- requires a mast, applicable hydraulic control valve, applicable hose group and the special placard item on order.
- VOIDS UL APPROVAL.

See Price List for 5 function option alternatives. For questions or other alternatives, contact SPED.

2 Auxiliary Function Attachment - All internal routing through mast. 1 function hydraulically actuated and 1 function hydraulically controlled via solenoid actuation. Includes necessary electrical cable, 3 function hydraulic hoses, components required for internal routing of electrical cable, and operator control switching for actuation of solenoid.

Requires 3-function valve and 3-function hose group on order.....	Q074-06	\$2,300.	16
---	---------	----------	----

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY **SPED PRICE LIST** **APPLICATIONS ENGINEERING DEPARTMENT**

S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

3 Auxiliary Function Attachment - All internal routing through mast. 1 function hydraulically actuated and 2 functions hydraulically controlled via solenoid actuation. Includes necessary electrical cable, 3 function hydraulic hoses, components required for internal routing of electric cable, and operator control switching for actuation of solenoid.

Requires 3-function valve and 3-function hose group on order.....	Q074-07	\$2,400.	16
---	---------	----------	----

4 Auxiliary Function Attachment - 2 functions hydraulically actuated and 2 functions hydraulically controlled via solenoid actuation. Includes necessary electrical cable, 4 function No. 6 hydraulic hoses, cable/hose reels and operator switching for actuation of solenoid.

Requires 4-function valve and 4-function hose group on order.....	Q074-03	\$2,500.	16
---	---------	----------	----

Placard - auxiliary functions. Order to include complete attachment description with hydraulic and electrical functions identified.

Requires special electric attachment group item on order.	Q074-04	N/C.	16
--	---------	------	----

ELECTRIC CIRCUIT BREAKER

Circuit breakers replace fuses. VOIDS UL APPROVAL	Q041-01	\$370.	12
---	---------	--------	----

ENGINE

Severe Duty Engine-GM 4.3L LT – LPG only. For applications where multiple shifts are required with little to no cool down period for lift trucks.

Requires GM LPG engine option on order.....	Q063-01	\$500.	12
---	---------	--------	----

ENGINE AIR FILTER

Precleaner mounted on overhead guard. NOT AVAILABLE with CAB.

With Diesel engine (VOIDS UL APPROVAL).....	Q004-01	\$1,260.	16
---	---------	----------	----

With LP/gas engine (VOIDS UL APPROVAL)	Q004-02	\$1,210	16
--	---------	---------	----

ENGINE SHUTDOWN SYSTEM

High water temperature and low oil pressure conditions. UL APPROVED.

Requires gas engine	Q069-01	\$830.	8
---------------------------	---------	--------	---

Requires LP gas engine	Q069-02	\$830.	8
------------------------------	---------	--------	---

Requires diesel engine.....	Q069-03	\$830.	8
-----------------------------	---------	--------	---

Seat actuated if operator does NOT set park brake. VOIDS UL APPROVAL.

Requires gas engine	Q069-08	\$700	8
---------------------------	---------	-------	---

Requires LP gas engine	Q069-09	\$700.	8
------------------------------	---------	--------	---

Requires diesel engine.....	Q069-10	\$955.	8
-----------------------------	---------	--------	---

ENGINE WARNING SYSTEM

High water temperature and low oil pressure conditions.

Includes warning light and buzzer – VOIDS UL APPROVAL	Q180-01	\$780	10
---	---------	-------	----


EXHAUST SYSTEM

Catalytic muffler replaces standard or catalyst added in exhaust line. VOIDS UL APPROVAL

Requires gas or LP gas engine on order	Q068-10	\$2,180.	16
--	---------	----------	----

Not Available with diesel engine.

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY **SPED PRICE LIST** **APPLICATIONS ENGINEERING DEPARTMENT**

S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

FILTER

Hydraulic tank breather filter- - 10 micron filter replaces standard	Q120-02	\$210	3
--	---------	-------	---

FIRE EXTINGUISHER

5 lb. dry chemical	Q080-01	\$350.	4
5 lb. CO ₂	Q080-02	\$520.	4
10 lb. dry chemical	Q080-03	\$375.	4
10 lb. CO ₂	Q080-04	\$560.	4

FORK

See Introduction for Notes.

FORK-HOOK TYPE, GYPSUM STYLE

NOTE: All gypsum forks listed include United States Gypsum specification tip and taper. Both outer edges of the fork blade are chamfered. Covered backing decreases the useable fork length 1/2". Backing material is bonded to a steel backing plate. Contacting the fork manufacturer for replacement backing is recommended. Fork capacities are as stated by the manufacturer in pounds at 24" load center per pair. Drawings of the applicable fork specifications are available on request from SPED. Contact SPED for forks less backing or for back heights and mounting types not listed.

Manufacturer: G.N.C. Division, Nelson Iron Works, Inc.	Backing Plate Steel: 11 gauge
Backing Mounting: Slide-in	Fork Material: SAE 8630
Backing Material: Non-marking Neoprene	Fork Type: Welded
Backing Durometer: 60	Ref. Drawing: S0004500 18

ITA Class	Section	Length	Capacity	Back Height			
IV	2"x8"	47.5"	13,300	48"	Q352-25	\$4,930. pr.	12
				60"	Q352-26	\$5,120. pr.	12
				72"	Q352-27	\$5,350. pr.	12
IV	2"x10"	47.5"	15,000	48"	Q352-28	\$5,890. pr.	12
				60"	Q352-29	\$6,080. pr.	12
				72"	Q352-30	\$6,380. pr.	12


FORK-HOOK TYPE, PALLET STYLE

Specify length in 2" increments on order.

ITA CLASS-IV 60mm x 150mm (2.5" x 6")

42" – 46" Length	Q086-32	\$1,070. pr.	12
48" Length	P.L.		
50" – 52" Length	Q086-33	\$1,160. pr.	12
54" Length	P.L.		
56" – 58" Length	Q086-34	\$1,230. pr.	12
60" Length	P.L.		
62" – 70" Length	Q086-35	\$1,360. pr.	12
72" Length	P.L.		
84" Length	Q086-51	\$1,930. pr.	12
96" Length	Q086-52	\$2,040. pr.	12

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

FORK-HOOK TYPE, POLISHED & TAPERED STYLE

Specify length in 2" increments on order.

ITA CLASS-IV 60mm x 150mm (2.5" x 6")

42" – 48" Length	Q380-35	\$1,370. pr.	12
50" – 54" Length	Q380-36	\$1,480. pr.	12
56" – 60" Length	Q380-37	\$1,580. pr.	12
62" – 72" Length	Q380-38	\$1,880. pr.	12

FOUNDRY CONSTRUCTION

Foundry Package NOT AVAILABLE on units with CAB.

Includes:

- 10 micron hydraulic tank breather filter
- 30-45 Amp alternator with sealed brushes & bearings with integral regulator.
- Heavy duty precleaner mounted on overhead guard

Options:

- Fire resistant hydraulic fluid (See Hydraulic Fluid)
- Magnetic drain plug in hydraulic tank to attract metal particles (Contact SPED)

Package:

Requires GM gas or LP gas engine and UL type G or LP option	Q349-20	\$1,605.	14
Requires Perkins diesel engine and UL type D options on order	Q349-24	\$1,315	14

FUEL INDICATOR-LOW LPG

Requires LP gas engine or dual fuel. UL APPROVED	Q165-01	\$580	6
--	---------	-------	---

FUEL SYSTEM

Note: CHANGES TO THE FUEL SYSTEM MAY RESULT IN VARIANCES TO PUBLISHED VALUES; CONTACT SPED IF CRITICAL.

Dual fuel – gas and LP gas. Includes production LP tank mounting bracket and LP fuel tank. Requires gas engine option on order.

NOT AVAILABLE with UL type GS option. Voids UL APPROVAL.	Q095-04	\$2,305.	6
---	---------	----------	---

LPG hose – stainless steel wire braid. UL APPROVED.

Requires LP gas engine option on order	Q095-03	\$155.	18
--	---------	--------	----

FUEL TANK

Gas tank filled with anti-freeze mixture and sealed for later conversion of LP gas to gas engine. Requires LP gas engine option on order. NOT AVAILABLE ON STOCK BASIC

Q060-01	\$500.	Prod.+2
---------	--------	---------

LP gas tank – aluminum. Requires LP gas engine option on order. FACTORY

INSTALLED ONLY	Q060-08	\$600	12
----------------------	---------	-------	----

GAUGE/METER

Engine Oil Pressure Gauge, Ammeter and Transmission Oil Temperature Gauge in addition to indicator lights.

Gauges with Lights	Q107-09	\$900.	8
--------------------------	---------	--------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

GROUND STRAP (STATIC STRAP)

Prevents build up of static electricity on frame and steer axle	Q108-01	\$70.	2
---	---------	-------	---

HYDRAULIC CONTROL VALVE

FACTORY INSTALLED ONLY. Requires applicable control valve on order. Attachment function identification BEZELS for special auxiliary function lever knobs will NOT be supplied unless a hydraulic attachment is ordered or the functions for an attachment to be installed in the field are supplied on order.

KEY:

- E = One lever with "ELECTRIC SWITCH" for two auxiliary hydraulic functions.
- H = One "H PATTERN" lever for two hydraulic functions.
- EH = One "H PATTERN" lever with "ELECTRIC SWITCH" for three auxiliary hydraulic functions.
- 1 = One lever for one hydraulic function.
- 2 = Two levers for two independent hydraulic functions.
- 1+H = Two levers, one independent and one "H PATTERN", for three auxiliary hydraulic functions.
- 1+E = Two levers, one independent and one "ELECTRIC SWITCH", for three auxiliary hydraulic functions.

Control Valve	Lift/Tilt Levers	Auxiliary Levers	Total Levers			
3 fct.	H	1	2.....	Q338-91	\$725.	10
4 fct.	H	H	2.....	Q338-99	\$150.	10
4 fct.	H	2	3.....	Q338-92	\$990.	10
4 fct.	2	2	4.....	Q338-22	\$350.	10
5 fct.	H	EH	2.....	Q338-98	\$725.	10
5 fct.	2	1+E	4.....	Q338-26	\$760.	10

HYDRAULIC FITTING-QUICK DISCONNECT

Male and female hydraulic fittings and tubes to allow an attachment to be quickly disconnected from the hydraulic supply for removal. Includes complete quick disconnect fittings for each function. Not normally required for integrally mounted attachments. 4-function disconnect requires 4-function hose group and control valve on order.

Vista 2-Stage Limited Free Lift Mast

One pair disconnect	-3 Function – High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-16	\$600.	14
	-4 Function – High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-17	\$600.	14
Two pair disconnects	-4 Function - High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-18	\$1,150.	14

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY **SPED PRICE LIST** **APPLICATIONS ENGINEERING DEPARTMENT**

S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

Vista 3-Stage Full Free Lift Mast

One pair disconnect	-3 Function– High Termination 3 rd function at top right side of carriage Not compatible with sideshift	Q187-22	\$570.	14
	-4 Function– High Termination 4 th function at top left side of carriage. 3 rd function used with sideshift.....	Q187-23	\$570.	14
Two pair disconnects	-4 Function High Termination 3 rd function at top right side and 4 th function at top left side of carriage. Not compatible with sideshift.	Q187-24	\$825.	14

HYDRAULIC FLUID

Fire resistant, Houghtosafe 620. FACTORY INSTALLED. CANNOT BE INSTALLED ON STOCK BASIC.

All internal combustion units require powershift transmission option on order

Note: Contact SPED for quoted mast for this option.....	Q140-01	\$2,880.	18
---	---------	----------	----

HYDRAULIC PRESSURE REGULATOR

3-position with gauge - used to regulate the pressure in the hydraulic attachment clamping circuit. 1st & 2nd positions are 50-1000 psi and the 3rd position is 500-3000 psi.

Requires applicable control valve and hose group on order.....	Q203-01	\$2,250.	12
--	---------	----------	----

HYDRAULIC VALVE-LOAD PROTECTOR

Prevents lift chains from going slack after depositing a load with a clamping type attachment.

Load protector	Q348-01	\$1,760.	10
----------------------	---------	----------	----

INDICATOR

Air restriction indicator.....	Q126-02	\$130.	4
--------------------------------	---------	--------	---

LIFTING EYES

Lifting eyes installed to allow truck to be lifted in approximately a level position with 20-foot equal length slings.

Mounting locations for sling clearance may increase the overall truck width. Contact SPED if overall width is critical.

Lifting Eyes	Q163-05	\$975.	12
--------------------	---------	--------	----

LIGHT-HEAD

NOT AVAILABLE with Price List light options (consult Truck Price List for light options offered prior to quoting to a customer).

UL APPROVED for all classifications. Maximum order quantity is 2 per truck.

Headlight – separate witch actuated	Q401-01	\$270. ea.	8
---	---------	------------	---

LIGHT-REAR DRIVING

NOT AVAILABLE with Price List light options (consult Truck Price List for light options offered prior to quoting to a customer).

UL APPROVED for all classifications. Maximum order quantity is 2 per truck.

Rear drive light – separate witch actuated	Q402-01	\$270. ea.	8
--	---------	------------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

LIGHT-STOP & TAIL

NOT AVAILABLE with Price List light options (consult Truck Price List for light options offered prior to quoting to a customer).

UL APPROVED for all classifications. Maximum order quantity is 2 per truck.

Stop/Tail light – separate witch actuated	Q403-01	\$265. ea.	8
---	---------	------------	---

LIGHT-STROBE

Continuous strobe, key switch actuated, UL APPROVED.

Overhead guard top mounted – increases truck height approximately 7".

Red.....	Q393-13	\$580.	12
----------	---------	--------	----

Amber.....	Q393-14	\$580.	12
------------	---------	--------	----

Mounted below overhead guard top.

Red.....	Q393-15	\$580.	12
----------	---------	--------	----

Amber.....	Q393-16	\$580.	12
------------	---------	--------	----

LIGHT-TURN SIGNAL

2 front and 2 rear turn signals. Available with headlight item Q401-01 and/or rear drive light item Q402-01.

Includes 2 stop/tail lights - VOIDS UL APPROVAL	Q404-02	\$950.	12
---	---------	--------	----

2 rear turn signals. Available with rear drive light item Q402-01.

Includes 2 stop/tail lights - UL APPROVED	Q404-03	\$800.	12
---	---------	--------	----

LOAD BACKREST EXTENSION

See Introduction for Notes.

Carriage or Attachment Width	Height 60"	Height 72"	
48"	Q166-22 460.	Q166-41 525.	14
54"	Q166-26 490.	Q166-42 550.	14
60"	Q166-30 520.	Q166-43 585.	14
78"	Q166-40 575.	Q166-44 650.	14

LUBRICANT/COATING

Electrical terminals sprayed with waterproof plastic	Q145-01	\$270.	24
--	---------	--------	----

Unpainted parts coated with low temperature grease.....	Q145-02	\$270.	24
---	---------	--------	----

Lift chains saturated with low temperature grease

Requires mast on order	Q145-03	\$270.	24
------------------------------	---------	--------	----

MAST

See Introduction for Notes.

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

MAST TILT

Mast forward tilt restricted to zero degrees at any lift height unless overridden by operator.

Tilt limit system VOIDS UL APPROVAL	Q285-10	\$2,010.	16
---	---------	----------	----

MAST TILT LIMITER

See Introduction for Notes.

MAST TILT-LIMITER BACK/FORWARD

Back and Forward tilt limiters are available in one-degree increments within the range shown. Specify the required degree of back/forward tilt on order. Consult the Industrial Truck Price List for production offering and usage restrictions before quoting. NOTE that if total degrees of tilt sums up greater than maximum P.L. total tilt, contact SPED for approval (i.e. 7° Forward + 8° Back = 15° Total tilt). FACTORY INSTALLED.

Minimum	Maximum				
5°	6°	Back Tilt.....	Q287-01	\$340. pr.	8
0°	6°	Forward Tilt	Q288-01	\$340. pr.	8

MAST TILT INDICATOR

Mechanical linkage system to indicate when the mast is vertical	Q286-01	\$790.	8
---	---------	--------	---

MAST TILT SPEED

Speed restrictor for use with load sustaining attachments to improve dynamic stability conditions.

Fitting type restrictor	Q096-02	\$225.	8
-------------------------------	---------	--------	---

NAMEPLATE

Additional Nameplate FACTORY INSTALLED. Nameplates will be provided with one load center giving the rating at maximum fork height and the maximum possible rating at a lower fork height. For NOT INSTALLED nameplates, submit "DEALER REQUEST FOR NAMEPLATE" form.

Metric Values with English Values Referenced	Q198-03	\$75 net	4
--	---------	----------	---

MIRROR

Price list cab options do not include this mirror.

Rearview mirror. NOT intended for reverse driving.	Q177-01	\$150.	8
---	---------	--------	---

OPERATOR SHIELD

Requires restricted back tilt, contact SPED.

Lexan Windshield mounted between front overhead guard legs	Q132-01	\$850.	12
--	---------	--------	----

OVERHEAD GUARD

Wire mesh added to top increases height approximately 3/8"	Q153-01	\$560.	10
--	---------	--------	----

Order for standard or special overhead guard.


OVERHEAD GUARD-LOWERED

OSHA recommended operator clearance from depressed seat to underside of overhead guard is 39" minimum.

Note: (+/- 0.75") tolerance for Overall Height (OAH)

Contact SPED with specific overall height.

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

OVERHEAD GUARD-RAISED

Note: (+/- 0.75") tolerance for Overall Height (OAH)
Contact SPED with specific OAH.

PAINT

ONE COLOR-Lead/Chromate free enamel paint on all normally painted exterior surfaces only. Exterior paint may be applied over standard color prepainted surfaces. Does NOT include interior surfaces. Paint color panel/chip must accompany orders for Non-Hyster colors. Hyster paint vendor to match color. Contrasting features, color and decals provided at Hyster's discretion. Hyster reserves the right to reject requirements for UNUSUAL NON-STANDARD Paints, PAINT SCHEMES or paints requiring SPECIAL APPLICATION TECHNIQUE. For paint schemes not listed or for special colors on NOT INSTALLED options pr special items, contact SPED.

Specify one paint color number for each item ordered.

Color Number: 1 = Hyster yellow

2 = Hyster white

3 = Hyster red

4 = Hyster black

5 = Non-Hyster color. Requires color panel/chip with order!

Orders received without such will be delayed!

Complete Truck (not forks or cab)-replace standard colors.....	Q191-08	\$1,145.	Prod.+2
Chassis/counterweight/hood -replace yellow & black	Q191-09	\$705.	Prod.+2
Chassis/counterweight/hood -replace yellow only.....	Q191-10	\$670.	Prod.+2
Chassis/counterweight/hood -replace black only	Q191-11	\$350.	Prod.+2
Overhead Guard -replace black only	Q191-05	\$160.	Prod.+2
Cab -replace standard color	Q191-07	\$230.	Prod.+2
Wheels -replace standard color	Q191-12	\$160.	Prod.+2
Mast/carriage/attachment -replace standard color	Q191-13	\$500.	Prod.+2
Load Backrest -replace standard color	Q191-14	\$120.	Prod.+2
Forks -replace standard color	Q191-06	\$130. pr.	Prod.+2

RAIN TOP

Plexiglas rain top mounted to top of overhead guard	Q238-01	\$565.	14
---	---------	--------	----

SEAT

Fabric covered non-suspension seat replacing vinyl covered non-suspension seat.

Includes seat adjustment and operator restraints.

Not recommended for outdoor applications without a cab.

Requires non-suspension seat option on order.	Q252-01	\$75.	12
--	---------	-------	----

SEAT-LOW PROFILE

Low profile seat replacing standard seat increases operator head clearance approximately 1".

Requires non-suspension seat option on order.

Vinyl covering	Q397-02	\$850.	12
Fabric covering.....	Q397-03	\$850.	12

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

SEAT-SUSPENSION

Grammer GS-12 semi-suspension seat, replacing standard non-suspension seat. Reduces the operator's head clearance approximately 1-1/2". Using the standard ("taller") OHG is recommended to ensure the operator head clearance. Consult technical guide for head clearance information. OSHA recommended operator clearance from depressed seat to underside of overhead guard is 39" minimum. Includes seat adjustment and operator restraints. Requires standard non-suspension seat option referenced on order.

VINYL COVERED SEAT.....	Q398-06	\$575	12
FABRIC COVERED SEAT.....	Q398-07	\$615.	12

(Not recommended for outdoor applications without a cab.)

Hyster "XM" style semi-suspension seat replacing standard seat. Reduces the operator's head clearance approximately 1/2". Using the standard ("taller") OHG is recommended to ensure the operator head clearance. Consult technical guide for head clearance information. OSHA recommended operator clearance from depressed seat to underside of overhead guard is 39" minimum. Includes seat adjustment and operator restraints. Requires non-suspension seat option on order.

VINYL COVERED SEAT.....	Q398-04	\$900.	12
FABRIC COVERED SEAT.....	Q398-05	\$950.	12

(Not recommended for outdoor applications without a cab.)

TIRES

See Introduction for Notes.

TIRE-DRIVE

Pneumatic Shaped Smooth Solid. 28 x 12.5-15.....	Q319-26	\$775. Pr.	12
Non-Marking Smooth Tread Solid. 28 x 12 x 22.....	Q319-07	\$380. Pr.	4

Requires static strap (ground strap) on order.

TIRE-STEER

Lug Tread Solid Steer 22 x 8 x 16	Q318-17	\$180. Pr.	4
Non-Marking Smooth Tread Solid Steer. 22 x 8 x 16	Q318-05	\$195. Pr.	4

Requires static strap (ground strap) on order.

TRACTION SPEED LIMIT

Traction speed limited to approximately 8.0 MPH when traveling in either forward or reverse. Proximity sensor monitors frequency of the differential gear teeth. When truck is traveling faster than 8.0 MPH, speed is limited by activating a sensor that controls the engine electronic governor. Full throttle is available provided the truck is traveling less than 8.0 MPH. Requires GM gasoline or LPG engine (with MSTs ignition) and powershift transmission on order.

VOIDS UL APPROVAL.	Q262-06	\$1,900.	18
-------------------------	---------	----------	----


Engine governed at reduced level to limit travel speed and reduce noise levels. Maximum engine RPM will be governed to reduced level by replacing standard electronic governor with special governor. Maximum travel, lift, and attachment speeds will be reduced from published specifications shown in technical guides. Requires GM engine option on order.

2300 RPM maximum.....	Q262-08	\$340.	Prod. + 2
2100 RPM maximum.....	Q262-09	\$390.	Prod. + 2
1900 RPM maximum.....	Q262-10	\$390.	Prod. + 2

High gear blocked out to limit travel speed. Physically limits ability to shift into high gear range. Consult the truck spec sheet for maximum speed in low range.

Requires 2-speed powershift transmission on order.....	Q262-05	\$235.	6
--	---------	--------	---

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



**HYSTER COMPANY
SPED PRICE LIST
APPLICATIONS ENGINEERING DEPARTMENT**

**S135-155XL2
SITDOWN-COUNTERBALANCED
INTERNAL COMBUSTION (IC)
CUSHIONED TIRE
SERIES CODE B024**

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

TRANSMISSION

Auxiliary transmission oil cooler.

Requires powershift transmission option and restricted back tilt on order..	Q297-03	\$850.	12
---	---------	--------	----

WARNING SYSTEM

BACKUP ALARM. Alarm sounds when key is on and direction control is in reverse mode only.

Requires powershift transmission option on order	Q222-14	\$500.	12
--	---------	--------	----

Requires manual transmission option on order	Q222-15	\$500.	12
--	---------	--------	----

BELL - WHEEL MOUNTED. Extends 3" beyond wheel.

Sounds when truck is traveling in reverse.	Q222-08	\$480.	12
---	---------	--------	----

ALARM – SEAT ACTUATED. Sounds when operator leaves the seat without setting the park brake. Deactivates when park brake is set. VOIDS UL APPROVAL.....


Q222-12	\$430.	12
---------	--------	----

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.

EFFECTIVE: 01/28/02

SPACESAVER- 31

REPLACES: 10/12/01



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT

S155XL₂-32
Special Configuration
SERIES CODE B024

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

B024 - S155XL₂-32 (Special Configuration)

Special S155XL₂ (15500# @ 32" L.C. BASIC). Frame length and wheelbase increases 8" more than the standard S155XL₂. The distance from the centerline of the steer axle to the rear of the counterweight is the same as the S155XL₂. Travel speeds will vary from the published speeds of the standard S155XL₂. Price is added on to the S155XL₂ basic truck from the P.L. Requires special front-end equipment, see below. Requires powershift transmission (054-02) and S155XL₂ basic truck (051-02) on order.

S155XL ₂ -32 Basic Truck.	Q020-02	\$ 16,600.	26
---	---------	------------	----

MAST-VISTA 2 STAGE LIMITED FREE LIFT

Contact SPED for complete mast specifications. Price is in addition to basic model.

MFH- 94.5"	Lowered- 92.5"	Free-Lift- 14"	Q430-13	\$ 11,600.	26
128"	109"	13"			
		Requires 5 degree back tilt limit.....	Q430-14	\$ 11,600.	26
134"	118"	25"	Q430-15	\$ 11,600.	26
162"	126"	13"	Q430-16	\$ 11,600.	26
174"	132"	13"	Q430-17	\$ 11,600.	26

CARRIAGE-HOOK TYPE, VISTA 2-STAGE LIMITED FREE LIFT MAST, NON ITA SPACING

	Fork Spacing				
Width	Inside	Outside			
48"	0"	44"	Q296-44	\$ 6,380.	26

ATTACHMENT-SIDESHIFT, HOOK TYPE, NON ITA SPACING

INTEGRAL MOUNTING TO MAST.

		Fork Spacing			
Mast	Width	Inside	Outside		
Vista 2-Stage LFL	48"	0"	44.0"		
10" of Sideshift, No Load backrest allowed.....				Q257-03	\$ 9,025. 26

ATTACHMENT-FORK POSITIONER, NON-SIDESHIFTING, HOOK TYPE, NON ITA SPACING

NOTE: All non-sideshifting fork positioners listed with simultaneous (Sim.) arm control (fork movement may be unequal) require a 3-function valve and 3-function hose group.

INTEGRAL MOUNTING TO MAST.

		Fork		Fork Spacing			
Mast	Width	Width	Inside	Outside	Control		
Vista 2-Stage LFL	48	"6	"0"	44.0"	Sim.....	Q088-01	\$ 9,255. 26


ATTACHMENT-FORK POSITIONER, SIDESHIFTING, HOOK TYPE, NON ITA SPACING

NOTE: All sideshifting fork positioners listed with simultaneous (Sim.) arm control (fork movement may be unequal) require a 4-function valve and 4-function hose group.

INTEGRAL MOUNTING TO MAST.

		Fork		Fork Spacing			
Mast	Width	Width	Inside	Outside	Control		
Vista 2-Stage LFL	48"	6"	0"	44.0"	Sim		
10" of Sideshift, No Load Backrest allowed						Q259-01	\$12,035. 26

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT	S155XL₂-32 Special Configuration SERIES CODE B024
--	--

*NOT ENGINEERED special items will INCREASE AVAILABILITY – See INTRODUCTION for complete details.

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

FORK-HOOK TYPE, PALLET STYLE

ITA			
Class	Section	Length	
NON	2.5" x 6"	48".....	Q086-45
NON	2.5" x 6"	54".....	Q086-46
NON	2.5" x 6"	60".....	Q086-47
NON	2.5" x 6"	72".....	Q086-48
NON	2.5" x 6"	84".....	Q086-49
NON	2.5" x 6"	96".....	Q086-50

LOAD BACKREST EXTENSION

See Introduction for Notes.

Load Backrest Extension 48" High, 48" Carriage	Q166-41	\$ 845.	26
--	---------	---------	----

HOSE GROUP-3 FUNCTION

Vista 2-stage LFL mast 3 function hose group. Hoses mounted external to mast.

Specify TOF lift height of mast on order. FACTORY INSTALLED.	Q373-01	\$ 670.	26
---	---------	---------	----

HOSE GROUP-4 FUNCTION

Vista 2-stage LFL mast 4 function hose group. Hoses mounted externally to mast.

Specify TOF lift height of mast on order. FACTORY INSTALLED.	Q374-01	\$1,260.	26
---	---------	----------	----

HOSE GROUP-5 FUNCTION

Vista 2-stage LFL mast 5 function hose group.

3rd and 4th Internal, 5th External	P.L. (070-05)		
--	---------------	--	--

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT	S155XL₂-SP Special Configuration SERIES CODE B024
--	--

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

B024 - S155XL2-SP (Special Configuration)

Special S155XL2 (18000# @ 24" L.C. Stretch Plus Basic). Frame length and wheelbase increases 8" more than the standard S155XL2. The distance from the centerline of the steer axle to the rear of the counterweight is the same as the S155XL2. Travel speeds will vary from the published speeds of the standard S155XL2. Price is added on to the S155XL2 basic truck from the P.L.. Requires special front-end equipment, see options below. Includes high load drive and steer tires that are the same size as the standard S155XL2 tires. Truck gives 6-degree forward and 8-degree back tilt unless equipped with a 95" or less OALH (lowered) mast, then truck gives 6 degree forward and 5-degree back tilt. Includes heavy-duty drive and steer axles as well as special tilt cylinders.

Requires powershift transmission and S155XL2 basic truck on order.

S155XL2-SP Basic Truck.....	020-03	\$27,200.	26
-----------------------------	--------	-----------	----

Note: Special Front-End Options for this truck are the same as listed for the [S180XL2](#) truck (see next page).

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT			S180XL₂ Special Configuration SERIES CODE B024
---	--	--	--

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

B024 - S180XL2 (Special Configuration)

Special S155XL2 (18000# @ 36" L.C. Basic). Frame length and wheelbase increases 15" more than the standard S155XL2. The distance from the centerline of the steer axle to the rear of the counterweight is the same as the 155XL2. Travel speeds will vary from the published speeds of the standard S155XL2. Price is added on to the 155XL2 basic truck from the P.L. Requires special front-end equipment, see options below. Includes high load drive and steer tires that are the same size as the standard S155XL2 tires. Truck gives 6-degree forward and 8-degree back tilt unless equipped with a 95" or less OALH(lowered) mast, then truck gives 6 degree forward and 5-degree back tilt. Includes heavy-duty drive and steer axles as well as special tilt cylinders.

Requires powershift transmission and S155XL2 basic truck on order.

S180XL2 Basic Truck.....	Q020-04	\$40,000.	26
--------------------------	---------	-----------	----

MAST-VISTA 2 STAGE LIMITED FREE LIFT

Contact SPED for complete mast specifications. Price is in addition to basic model.

MFH- 95"	Lowered- 100.5"	Free-Lift- 12.5"	Q430-18	\$22,500.	26
128"	117"	12.5"	Q430-19	\$22,500.	26
134"	120"	12.5"	Q430-20	\$22,500.	26
162"	134"	12.5"	Q430-21	\$22,500.	26
180"	143"	12.5"	Q430-22	\$22,500.	26

CARRIAGE-PIN TYPE, VISTA 2-STAGE LIMITED FREE LIFT MAST

	Fork Spacing				
Width	Inside	Outside			
48"	0"	44"	Q340-08	\$10,010.	26

ATTACHMENT-SIDESHIFT, PIN TYPE

NOTE: All sideshifts listed require 3-function valve and 3-function hose group. Requires pin type forks.

INTEGRAL MOUNTING TO MAST.

		Fork Spacing			
Mast	Width	Inside	Outside		
Vista 2-Stage LFL	48"	0"	44.0"		
8" of Sideshift, No Load backrest allowed.....	Q258-43	\$14,560.	26		

ATTACHMENT-FORK POSITIONER, NON-SIDESHIFTING, PIN TYPE

NOTE: All non-sideshifting fork positioners listed with simultaneous (Sim.) arm control (fork movement may be unequal) require a 3-function valve and 3-function hose group.

INTEGRAL MOUNTING TO MAST.

		Fork	Fork Spacing			
Mast	Width	Width	Inside	Outside	Control	
Vista 2-Stage LFL	48	"8	"0"	44.0"	Sim.....	Q089-89
						\$14,950.
						26

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.

EFFECTIVE: 01/15/01

REPLACES: 07/03/00



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT			S180XL₂ Special Configuration SERIES CODE B024		
---	--	--	--	--	--

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

ATTACHMENT-FORK POSITIONER, SIDESHIFTING, PIN TYPE

NOTE: All sideshifting fork positioners listed with simultaneous (Sim.) arm control (fork movement may be unequal) require a 4-function valve and 4-function hose group.

INTEGRAL MOUNTING TO MAST.

Mast	Width	Fork Width	Fork Spacing Inside	Fork Spacing Outside	Control			
Vista 2-Stage LFL	48"	8"	0"	44.0"	Sim			
8" of Sideshift, No Load Backrest allowed						Q260-39	\$15,620.	26

FORK-PIN TYPE, PALLET STYLE

Only for use with S155XL2-SP/S180XL2 carriage and attachments.

Note: (a) Forks for Fork Positioner only.

Section	Length			
2.75"x 8"	48"		Q330-88	\$3,700.pr. 26
"	54"		Q330-89	\$3,790.pr. 26
"	60"		Q330-90	\$3,870.pr. 26
"	72"		Q330-91	\$4,030.pr. 26
"	96"		Q330-92	\$4,280.pr. 26
2.75" x 8"(a)	48"		Q382-01	\$3,950.pr. 26
"	54"		Q382-02	\$4,030.pr. 26
"	60"		Q382-03	\$4,120.pr. 26
"	72"		Q382-04	\$4,300.pr. 26
"	96"		Q382-05	\$4,620.pr. 26

LOAD BACKREST EXTENSION

See Introduction for Notes.

Load Backrest Extension-48"High, 48" Carriage	Q166-43	\$845.	26
---	---------	--------	----

HOSE GROUP-3 FUNCTION

Vista 2-stage LFL mast 3 function hose group. Hoses mounted externally to the mast. Does not increase OALH of the mast. Specify TOF lift height of mast on order. FACTORY INSTALLED.

.....	Q373-02	\$670.	26
-------	---------	--------	----

HOSE GROUP-4 FUNCTION

Vista 2-stage LFL mast 4 function hose group. Hoses mounted externally to the mast. Does not increase OALH of the mast. Specify TOF lift height of mast on order. FACTORY INSTALLED.

.....	Q374-02	\$1,260.	26
-------	---------	----------	----

HOSE GROUP-5 FUNCTION

Vista 2-stage LFL mast 5 function hose group. Hoses mounted externally to the mast. Does not increase OALH of the mast. Specify TOF lift height of mast on order. FACTORY INSTALLED.

.....	Q375-01	\$1,805.	26
-------	---------	----------	----

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.

EFFECTIVE: 01/15/01

REPLACES: 07/03/00



HYSTER COMPANY SPED PRICE LIST APPLICATIONS ENGINEERING DEPARTMENT	S200XL₂ Special Configuration SERIES CODE B024
---	--

Description	Item No.	Price	Availability (In Weeks *)
-------------	----------	-------	------------------------------

B024 - S200XL2 (Special Configuration)

Special S155XL2 (20000# @ 24" L.C. Basic). Frame length and wheelbase increases 15" more than the standard S155XL2. The distance from the centerline of the steer axle to the rear of the counterweight is the same as the S155XL2. Travel speeds will vary from the published speeds of the standard S155XL2. Price is added on to the S155XL2 basic truck from the P.L. Includes high load drive and steer tires that are the same size as the standard S155XL2 tires. Truck gives 6-degree forward and 8-degree back tilt unless equipped with a 95" or less OALH (lowered) mast, then truck gives 6 degree forward and 5-degree back tilt. Includes heavy-duty drive and steer axles as well as special tilt cylinders. Requires special front-end equipment, contact Applications Engineering. Requires powershift transmission and S155XL2 basic truck on order.

S200XL2 Basic Truck..... Contact Applications Engineering

Prices, availability, and lead times are subject to change without notice. The pricing, availability, and lead time information contained in NOMS and HERO is the correct and current information. Be sure to download your HERO price book at least once a week. It is also recommended that you verify quotes against the HERO information before giving them to a prospective customer.